



Segment 1	Alternative A	Alternative B	Alternative C
Meridian to Bull Headley	Multi-use Path, Swales	Sidewalk 1-Side, Swales	Sidewalk both-sides, Swales
Social / Cultural Impacts			
Residential Impacts (parcels)	41	40	74
Residential Impacts (acres)	4.24	2.92	6.00
Residential Relocations (number)	0	0	0
Neighborhood Impacts (parcels)	0	0	0
Neighborhood Impacts (acres)	0.00	0.00	0.00
Business Impacts (parcels)	1	1	2
Business Impacts (acres)	0.17	0.13	0.47
Business Relocations (number)	0	0	0
Undeveloped Parcels (number)	8	8	14
Undeveloped Impacts (acres)	1.06	0.76	1.79
Municipal Parcels (number)	0	0	2
Municipal Parcels (acres)	0.00	0.00	0.20
Stormwater Pond Impacts (parcels)	0	0	0
Stormwater Pond Impacts (acres)	0.00	0.00	0.00
Total ROW (acres)	5.47	3.81	8.46
Pedestrian/Bicycle Facilities (PED/BIKE/BOTH)			
Maintenance of Traffic (\$, \$\$, \$\$\$)	BOTH	PED	PED
Environmental Impacts			
Wetlands Impacts (acres)	0.2	0.2	0.4
Floodplains (acres)	0.0	0.0	0.0
Threatened and Endangered Species (high, medium, low)	Low	Low	Low
Potential Contaminated Sites (number)	0	0	2
Noise Impacts (low, moderate, high)	Low	Low	Low
Estimated Costs			
Construction Cost (dollars)	\$ 789,000.00	\$ 491,000.00	\$ 917,000.00
Final Design and CEI (dollars)	\$ 157,800.00	\$ 98,200.00	\$ 183,400.00
ROW Cost (dollars)	\$ 4,236,400.00	\$ 4,072,000.00	\$ 7,824,000.00
<b>Total Cost \$\$</b>	<b>\$ 5,183,200.00</b>	<b>\$ 4,661,200.00</b>	<b>\$ 8,924,400.00</b>
Segment 2	Alternative A	Alternative B	Alternative C
Bull Headley to Tekesta	Multi-use Path, Swales	Sidewalk 1-Side, Swales	Sidewalk both-sides, Swales
Social / Cultural Impacts			
Residential Impacts (parcels)	0	0	9
Residential Impacts (acres)	0.00	0.00	3.06
Residential Relocations (number)	0	0	0
Neighborhood Impacts (parcels)	6	5	7
Neighborhood Impacts (Acres)	1.94	1.20	1.32
Business Impacts (parcels)	6	4	5
Business Impacts (Acres)	0.44	0.30	0.37
Business Relocations (number)	0	0	0
Undeveloped Parcels (number)	3	3	4
Undeveloped Impacts (acres)	0.59	0.43	0.50
Municipal Parcels (number)	0	0	0
Municipal Parcels (acres)	0.00	0.00	0.00
Stormwater Pond Impacts (parcels)	0	0	0
Stormwater Pond Impacts (acres)	0.00	0.00	0.00
Total ROW (acres)	2.98	1.93	2.20
Pedestrian/Bicycle Facilities (PED/BIKE/BOTH)			
Maintenance of Traffic (\$, \$\$, \$\$\$)	BOTH	PED	PED
Environmental Impacts			
Wetlands Impacts (acres)	0.2	0.2	0.3
Floodplains (acres)	0.0	0.0	0.0
Threatened and Endangered Species	Low	Low	Low
Potential Contaminated Sites (number)	1	1	1
Noise Impacts (low, moderate, high)	Low	Low	Low
Estimated Costs			
Construction Cost (dollars)	\$ 526,000.00	\$ 332,000.00	\$ 615,000.00
Final Design and CEI (dollars)	\$ 157,800.00	\$ 99,600.00	\$ 184,500.00
ROW Cost (dollars)	\$ 1,636,900.00	\$ 1,244,300.00	\$ 2,324,500.00
<b>Total Cost \$\$</b>	<b>\$ 2,320,700.00</b>	<b>\$ 1,675,900.00</b>	<b>\$ 3,124,000.00</b>
Segment 3	Alternative A	Alternative B	Alternative C
Tekesta to Thomasville	Swales, Widen South	Curb and Gutter, Widen South	Curb & Gutter, Widen North
Social / Cultural Impacts			
Residential Impacts (parcels)	14	13	14
Residential Impacts (acres)	5.42	3.22	0.44
Residential Relocations (number)	0	0	0
Neighborhood Parcels (number)	4	3	4
Neighborhood Impacts (acres)	3.41	0.60	6.71
Business Impacts (parcels)	3	3	4
Business Impacts (acres)	1.83	1.21	0.42
Business Relocations (number)	4	0	0
Undeveloped Parcels (number)	3	3	0
Undeveloped Impacts (acres)	1.10	0.62	0.00
Municipal Parcels (number)	0	0	0
Municipal Parcels (acres)	0.00	0.00	0.00
Stormwater Pond Impacts (parcels)	0	7	7
Stormwater Pond Impacts (acres)	0.00	1.75	1.75
Total ROW (acres)	11.76	7.40	9.32
Pedestrian/Bicycle Facilities (PED/BIKE/BOTH)			
Maintenance of Traffic (\$, \$\$, \$\$\$)	BOTH	BOTH	BOTH
Environmental Impacts			
Wetlands Impacts (acres)	0.3	0.3	0.3
Floodplains (acres)	0.0	0.0	0.0
Threatened and Endangered Species	Low	Low	Low
Potential Contaminated Sites (number)	0	0	0
Noise Impacts (low, moderate, high)	Low	Low	Moderate
Estimated Costs			
Construction Cost (dollars)	\$ 4,690,000.00	\$ 6,878,000.00	\$ 6,878,000.00
Final Design and CEI (dollars)	\$ 1,641,500.00	\$ 2,407,300.00	\$ 2,407,300.00
ROW Cost (dollars)	\$ 2,639,600.00	\$ 2,802,800.00	\$ 2,954,600.00
<b>Total Cost \$\$</b>	<b>\$ 8,971,100.00</b>	<b>\$ 12,088,100.00</b>	<b>\$ 12,239,900.00</b>